



Release Notes

Illustra 600 Series Compact Mini-Dome, Mini-Bullet, LT Bullet and 2 MP Micro cameras Firmware Release 2.1.7

| Model | Description | Product Data |
|---------------|---|--|
| ADCi600-M111 | Illustra Pro 1MP Compact Mini-Dome | Visit the Illustra Cameras web site www.illustracameras.com to download datasheets and other documentation in PDF format. |
| ADCi610-M111 | Illustra Pro 2MP Compact Mini-Dome | |
| ADCi610E-M111 | Illustra Pro 2MP Compact Mini-Dome, 3.8mm | |
| ADCi610-M022 | Illustra Pro 2MP Mini-Bullet | |
| IPL02B2BNWIY | Illustra Pro LT 2MP Bullet, 3-9mm | |
| IPL02B1BNWIY | Illustra Pro LT 2MP Bullet, 2.8-12mm | |
| IPS02HFANWSY1 | Illustra Pro 2MP Micro, 2.6mm | |
| IPS02HFANWSY2 | Illustra Pro 2MP Micro, 2.8mm | |
| IPS02HFANWSY3 | Illustra Pro 2MP Micro, 3.7mm | |

Note

In case of discrepancy, the information in this document supersedes the information in any document referenced herein.

Contents

| | |
|---|----------|
| What's in this Release | 1 |
| Firmware Upgrade | 2 |
| Known Limitations and Issues | 3 |
| Contact Information..... | 4 |

What's in this Release

Firmware Release: ADCi6x0M V2.1.7

Enhancement to Zoom/Focus control for Pro LT bullet on ExacqVision Server integration.

Previous Firmware Releases

ADCi6x0M V2.1.5.55

2.1.5.55 Updates:

- (1) Support for a new image sensor.

ADCi6x0M V2.1.2.1094

2.1.2 Updates:

| Item | Description |
|------|--|
| 1. | Support for new Illustra camera models – Illustra Pro 2MP Micro cameras. |

ADCi6x0M V2.0.15.1063

2.0.15 Updates:

- (1) Illustra Pro 2MP LT Bullet – Zoom and Focus are now supported by API3.

ADCi6x0M V2.0.12.1057

2.0.12 Updates:

- (1) Support for a new Illustra camera model – Illustra Pro 2MP LT Bullet.
- (2) Support for Applications – ExacqVision Edge.

ADCi6x0M V1.2.4.1001

1.2.4 Updates:

- (1) Support for new model – ADCi610-M022 Compact Mini-Bullet.
- (2) Enhancement – Open SSL Vulnerability (Heartbeat Bug) fix.
- (3) New Feature – Di / Do, IR Illumination control – Compact Mini-Bullet only.

ADCi6x0M V1.1.9.933

1.1.9 Updates:

- (1) New features – Corridor Mode, IP Filtering, ONVIF relay attack protection, Event Search.
- (2) Enhancements – Min shutter speed 1/10000 sec, Manual WDR.

ADCi6x0M V1.0.8.12

Initial Camera Firmware Release.

Firmware Upgrade

Note:

As part of the Firmware upgrade procedure we recommend users refresh their browser cache.

Camera firmware must be downloaded from the [Illustra website](#) and can be installed using either Illustra Connect or the utility in the camera web interface.

Note:

Ensure your camera does not lose power during the firmware upgrade process.

Using Illustra Connect

1. Install and launch the Illustra Connect software utility.
 2. Select the camera needing firmware upgrade from the list of found cameras.
 3. Right click on the camera in the list and select Upgrade Firmware.
 4. Select Choose File to find the firmware upgrade file on your system.
-

Note:

The file-type selection filter may need to be changed to "All Files".

Using the Camera Web Interface

1. Using Internet Explorer, connect to the camera IP address.
2. At the top of the page, select Setup.
3. Select Maintenance and then select Firmware Upgrade.
4. Select Browse and find the firmware file.
5. Select Start and wait until the progress bar is complete.

Known Limitations and Issues

The table below highlights known new limitations or issues against the firmware. Known limitations and issues may exist from previous releases. Please refer to the specific release for the appropriate information.

| Description | Note |
|---|--|
| Illustra 610M Compact Mini-Dome / Mini-Bullet camera does not support MS Internet Explorer 11. | Use Internet Explorer 8, 9 or 10 or use Compatibility mode in IE 11. |
| UDP_i6x0_LT: ExacqVision Integration: SD card recording features on the camera (FTP, SD Clip Recording) will not be available after installing Edge application | This is because the SD Card is being used to run ExacqVision Edge. |
| Removing the SD card causes the camera to reboot if a user does not click 'Eject' first on the GUI | Refer to Technical Bulletin TB-00290-00-130701. |
| When corridor mode is configured the camera will return approximately half of the FPS configured | There is no work-around. |
| When streaming MJPEG 30FPS 1080P the image will freeze and drop FPS. | Lower the Quality to 50 OR lower the resolution. |
| The LT bullet tries to keep an object of interest in approximate focus during the zoom operation. In some instances the camera will not zoom unless the focus is adjusted on the subject. | If the zoom action fails please try to re-focus the camera and then adjust the zoom once the camera is at the new focus point (lens limitation). |
| The LT bullet supports manual focus and Zoom control integration on ExacqVision Server using camera FW 2.1.7 or above. For autofocus integration support the ExacqVision Server must be version 9.1 (to be released March 2018) or above. | |

Contact Information

If you have any questions please contact Tyco Security Products Technical Services at:

Toll Free: 800-507-6268, Option 2

International: 561-912-6259, Option 2

Alternative Number: 800-392-2873

Fax: 450-444-2029

Hours: 08:00 – 20:00 EST

Email: adtechservices@tycoint.com

Website: www.illustracameras.com

In Europe, Middle East and Africa, contact Technical Support at:

Toll Free: +800 CALLTYCO or +800-2255 8926

Direct: +31 475 352 722

Hours: 08:00 – 18:00 CET

Email: tsp.emea.video.support@tycoint.com

Website: www.tycosecurityproductsemea.com

Website: www.calltyco.com

Local Direct dial numbers:

UK 08701 238 787

Bahrain 800 04127

France 0800 90 79 72

Greece 00800 31 229 453

Spain 900 99 39 61

Russia 810 800 20 521 031

Germany 0800 1806 757

Turkey 00800 31 923 007

Italy 0800 874 091

United Arab Emirates 800 0310 7123

Belgium 0800 76 452

Israel 03 345 6868

Ireland 021 480 1122

In Latin America and Caribbean, contact Technical Support at:

Southern Latin America

Contact: Cesar Cristal

Phone: +54-11-4711-8711

Cell: +54911-6452-7573

Email: ccristal@tycoint.com

Brazil

Contact: Mauro Altino

Phone: +55-11-3443-7232

Cell: +55-11-8998-9770

Email: maltino@tycoint.com

Northern Latin America & Caribbean

Contact: Hildebrando Duran

Phone: +57-1638-6278

Cell: +57-317668-9590

Email: hiduran@tycoint.com

Mexico

Contact: Marco Antonio Salguero

Phone: +52-55-5488-8092

Cell: +52-55-1473-4946

Email: msalguero@tycoint.com

In Asia Pacific, contact Technical Support at:

Toll Free: +800 CALLTYCO or +800-2255 8926

Direct: +86 21 60 23 0650

China Only Hotline: 400 671 1528

India Only Hotline: 1 800 1082 008

Hours: 08:00 – 17:00 CST

Email: apac.support@tycoint.com

Information furnished by Tyco Security Products is believed to be accurate and reliable. However, no responsibility is assumed by Tyco Security Products for its use, nor any infringements of other rights of third parties which may result from its use. No license is granted by implications or otherwise under any patent rights of Tyco Security Products.